


## **SOUTH WILLAMETTE Street Improvement Plan**

Refine the Preferred Alternatives

# Project Schedule and Outreach





# Alternatives Overview



# Alternatives Development Process

#### Stakeholder Outreach

 Conversations with business and property owners, residents, and users of all modes (August, February, May)

### Community Concerns

- Community Forum #1 "Explore the Alternatives" (November)
- Community Forum #2 "Evaluating the Alternatives" (February)

#### Committee Feedback

 Technical Advisory Committee, including LTD, EWEB and Emergency Responders (November, January, May)

### Elected/Appointed Official Oversight

- Planning Commission Meeting (November)
- City Council Work Session (January)



# **Alternatives Screening**

#### Tier 1

- Evaluation of community priorities
- Identification of broad level tradeoffs
- Assessment using qualitative tool (scoring criteria)

#### Tier 2

More details and rigorous analysis of the designs

Tier 1: 6 alternatives  $\rightarrow$  3 alternatives

Tier 2: 3 alternatives → Draft Plan (preferred alternative)



### What We've Heard

- Fix the drainage
- Improve the sidewalk environment (utilities, uneven pavement)
- Better bicycle access
- Minimize negative impacts to businesses (construction, parking loss, traffic shift)
- Make it safer (speeding, turn conflicts, bikes on sidewalks)




### For All Alternatives


- New roadway pavement
- Drainage improvements
- Improved sidewalks
- Improvements for nearby bike routes
- Enhanced crossing options for bicycles & pedestrians
- Driveway modifications (TBD)



Existing and Proposed Nearby Bicycle Routes








# Alternative Concepts










### 4-Lane

- Maintains existing 4 travel
   lanes
- Left-turning vehicles block travel lanes
- 9' sidewalks
- No bike lanes
- Maintains 11' outside travel lane for buses

### Alternative 1










# 3-Lane with Bike Lanes

- 3 travel lanes (1SB, 1NB, 1 center)
- 9' sidewalks
- Bike lanes
- 10' travel lanes are narrow for buses and trucks
- Center turn lane offers opportunities for design treatments
- Intersections and traffic signals would need to be reconfigured

## **Alternative 3**







# 3-Lane with Wide Sidewalks

- 3 travel lanes (1SB, 1NB, 1 center)
- 13' sidewalks
- Wide sidewalks provide design treatment options
- No bike lanes
- Maintains 11' outside travel lane
- Center turn lane offers opportunities for design treatments
- Intersections and traffic signals would need to be reconfigured


### **Alternative 5**





# Corridor Overview

 Design for continuity in transition area near
 29<sup>th</sup> Ave





# Transportation Analysis



# Transportation Analysis Overview

- 2018 P.M. peak hour traffic
- Intersection operations standard

```
Citywide: LOS D Downtown: LOS E
```

- Traffic operations similar for Alts 3 & 5
- Multimodal Level of Service (LOS) for Auto, Pedestrian, Bicycle, Transit




# **Traffic Finding**

- 3 lanes is not enough for peak traffic at 29<sup>th</sup> Ave intersection
- Level of Service F
- Modify design for 3-lane Alternatives to maintain 2 southbound lanes at 29<sup>th</sup> Ave



# Design Modification at 29<sup>th</sup> Ave

- Applied to Alt 3 & 5
- 2 Southbound through lanes through to 32<sup>nd</sup> Ave
- Minimize capacity reduction at 29<sup>th</sup> Ave for p.m. peak direction traffic (southbound)
- Alt 3 would include bike lanes




Alt 5



# Motor Vehicle Lanes


Modified design for Alt 3 & 5
 would provide 4 lanes at 29<sup>th</sup> Ave
 intersection





### **Travel Time**

- Average travel times between 24<sup>th</sup> and 32<sup>nd</sup> Ave would be ~30 seconds longer, southbound and northbound, for Alt 3 & 5 (compared to Alt 1)
- Travel time would be more reliable in Alt 1 (less variance)






# Intersection Operations

- 29<sup>th</sup> Ave intersection operates at LOS D with 5 lanes (Alt 1)
- 4 lanes may be adequate for peak traffic at 29<sup>th</sup>
   Ave intersection if LOS E (downtown standard) is accepted
- 3 lanes would be inadequate (LOS F)
- All other intersections operate with LOS D or better for all Alts



# Vehicle Queuing


- Vehicle queues will
  ~double for Alts 3 & 5
- Illustration shown for southbound at 27<sup>th</sup> Ave.





### Potential Traffic Shift in Alt 3 & 5

- Shift in average daily traffic away from Willamette St is estimated to be 100 to 500 vehicles in 2018
- 1-3% of daily traffic





### Potential Traffic Shift

P.M. Peak hour shift in Alt 3 & 5 is estimated to be
25 to 100 vehicles

### Where to?

- East:  $\sim 2/3$  east to Hilyard & Amazon
- West: ~1/3 west to Lincoln, Jefferson, Adams
   &Polk



### Multimodal LOS


- Alternatives represent tradeoffs for level of comfort by mode of travel
- Automobile and transit modes: Alt 1 provides most speed and comfort
- Bicycles: Alt 3 (bike lanes) provides most comfortable option for travel by bicycle
- Pedestrians: Alt 5 (wider sidewalks)



# Proposed Design Refinements





# Potential Crossing Enhancements





# Design Option on 24th Ave







# Design Option at Woodfield Station

- New traffic signal (all Alts)
- Provides pedestrian crossing between 29<sup>th</sup>
   Ave and 27<sup>th</sup> Ave (~1,000 feet)
- Improves turning opportunities at Woodfield Station Driveway
- Close spacing of intersections requires further evaluation - Special design considerations & coordination with 29<sup>th</sup> Ave traffic signal



# Design Option at 29th Place

- Crossing provided for bike route southbound from Oak St, where existing northbound bike lane ends
- Provides pedestrian crossing between  $29^{th}$  Ave and 32nd Ave ( $\sim 1,500$  feet)
- Higher priority
   without bike
   lanes on
   Willamette St
   (Alt 1 & 5)





## Potential Further Refinements



### **Further Refinements**

- Intersection traffic controls (e.g., roundabouts, signals)
- Sidewalk characteristics (e.g., utilities, landscaping)
- Other crossing treatments
- Traffic signal design at Woodfield Station
- Bus pullouts



### **Enhance Sidewalk Environment**

- Stormwater treatments
- Utility relocation
- Street lighting
- Bike parking
- District signing
- Landscaping/vegetation
- Limited options for 9' sidewalk (Alt 1 & 3)
- Wider sidewalks (13' in Alt 5) can provide more amenities (e.g., café seating)





### Roundabouts

- Remain as option for
   24<sup>th</sup>, 25<sup>th</sup>, 27<sup>th</sup> Ave intersections
- 29<sup>th</sup> Ave would require multi-lane roundabout
- Property impacts at intersections
- Design for emergency response
- Concerns about available capacity at 24<sup>th</sup> & 27<sup>th</sup> Ave approaches







# Cost Estimates



### Cost Estimates

• Alt 1: \$4.1M

• Alt 3: \$4.2M

• Alt 5: \$4.8M

Included: \$2.1M paving & stormwater project from 24<sup>th</sup> Ave to 29<sup>th</sup> Ave

Not included: \$2.6M for utility relocation

Note: Costs shown are high-level planning estimates in 2013 dollars, subject to change.



# Next Steps



# Tier 2 Screening

- Meet with community and key stakeholders
- Brief City Council in June
- Analyze input on preferred crosssection and design refinements
- Refine design for preferred alternative



# Group Discussion

What information did you hear that helps you select and refine an alternative?

